Sl. No.	Items of work	Unit	Quantity	Rate	Cost
				Rs. a. p.	Rs.
6	Supplying and fixing stone pillars dressed, 10″ square, 9¾′ high as per design of pillars in ground floor verandah, including base and capital complete ..	No.	6		
7	R.B.C. terrace for a span of 10 feet	Sqr.	6.78		
7a	R.B.C. terrace for a span up to 12 feet	,,	3.92		
7b	R.C.C. (1 : 2 : 4) roofing designed to withstand a superload of 50 lbs. per sq. ft., with weatherproof finishing at top as per standard specifications and ceiling plastering including coving, whitewashing, etc., complete, deductions *vide* (7) and (7a) ..	,,	10.70		
8	Slab chajja cornice with nice dressing and moulding as per design, having a projection of about 2 feet from wall surface	S.ft.	98		
9	Two line dressed stone string course fixed in lime mortar as per design to be specified, 9″ to 10″ deep	R.ft.	101½		
10	Chunam plastering 3 coats for stone walls ..	Sqr.	9.24		
10a	Chunam plastering 2 coats for brick walls ..	,,	26.38		
11	Cement pointing to stone masonry walls with neat horizontal and vertical cut lines, including raking joints to a depth of ½ inch	,,	10.00		
12	Flooring finish with 1½″ cement concrete and ½″ plaster red cement mixture finished smooth with or without cut lines as ordered including levelling the top surface of existing roof before laying concrete	,,	8.12		
13	Whitewashing two coats	,,	35.66		
13a	Colour washing two coats over one coat of whitewashing	,,	35.66		
14	Preparing and fixing Teakwood stair case in 1″ thick planks 12″ tread, 6″ rise width between 3 ft. and 4 ft. with ornamental beading at ends with Teakwood turned balusters and Teakwood hand rails and Teakwood ornamental newels at bottom and top, etc., complete	S.ft.	90		
14a	R.C. Cantilever or slab stairs as per specifications, width between 3 ft. and 4 ft.	,,	90		
15	Providing and fixing ornamental M. S. railings with Teakwood hand railing 2½ ft. high	R.ft.	14		
16	Size stone in lime mortar parapet wall 9″ thick with base and coping stones and 2 ft. high including pointing on all sides	,,	101½		
17	Lac factory green paint, two coats	Sqr.	3.80		
18	Deluxe varnish two coats	,,	4.33		
19	Providing Tata's tested R. S. beams in verandah over columns including hoisting, and fixing, complete ..	Cwt.	6.20		
20	Boxing girders in brick in cement mortar (1 : 3) including wire netting, plastering, whitewashing, etc., complete	R.ft.	19		

M. K. RAJAM IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE SPECIAL DUTY OFFICER, BIRTHDAY FESTIVITIES.

Tender Notice No. O. 2758, *dated 6th May* 1940.

Notice is hereby given that sealed tenders will be received by 3 P.M., at the Office of the Special Duty Officer, Birthday Festivities, Indian Guests' Quarters, Mysore, up to 24th May 1940, for constructing about half a dozen temporary latrines, about ten motor sheds and about 20 to 25 temporary sheds at Mysore to serve as kitchen and bath rooms for the use of Guests and Representative Assembly Members to be accommodated in the several buildings. The specifications of the sheds and latrines are given below. The work should be completed by the end of 31st May 1940.

2. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for the construction of temporary sheds at Mysore", in default of which tenders will be rejected.

3. The final acceptance of any tender will rest with the Special Duty Officer, Birthday Festivities, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

4. Within three days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond with a security deposit of Rs. 50, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

5. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Special Duty Office at the Indian Guests' Quarters, Mysore, in due course. No enquiries regarding the acceptance of a tender will receive any reply.

6. On acceptance of any one of the tenders, the earnest money on rejected tenders will be returned.

Specifications.

1. Each kitchen and bath shed to measure about 20′×10′ divided into three compartments made out of thatti mat walls and doors and thatched roof with grass on the top. Each shed to consist of one kitchen cistern and one bath cistern and one big oven and two small ovens. Ground to be cleaned and to be washed with cowdung and the drainage around the shed arranged for.

2. Each motor shed to measure about 18′×12′ made out of thatti mat walls and doors and thatched roof with grass on the top. Ground to be cleaned and scraped and the drainage around the shed arranged for.

3. Each latrine to measure about 4′×5′ built of thatti mat walls and provided with a pit 3′×1′. The ground to be cleaned and scraped.

4. The materials to be used may be taken by the contractor after the occasion and the grounds levelled and made clean and tidy after removal.

M. M. C. SRIRANGACHAR,
Special Duty Officer.

DEPARTMENT OF INDUSTRIES AND COMMERCE IN MYSORE, BANGALORE.

OFFICE OF THE *Ex-Officio* CONTROLLER OF PATENTS AND DESIGNS.

Notice dated 7th May 1940.

REGISTRATION OF ASSIGNMENTS.

Assignment affecting the interests of the original Patentee have been registered in the following case:—

No. 87—1933-34 .. The Chief Conservator of Forests in Mysore, Bangalore.

B. G. A. MUDALIAR,
Ex-Officio Controller.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Notification No. G. N. 38, *dated 7th May* 1940.

FANS.

To

The Electrical Firms.

GENTLEMEN,

Please be good enough to quote your best price for the supply of the following, delivered at destinations as noted against each item, and send your quotation so as to reach this office not later than the 25th of May 1940, 12 NOON.

Earliest time of delivery need be stated.

The supply on this enquiry will be subject to the conditions that pertain to Local Purchases in this Department.

On the face of the envelope should be superscribed the words "Tender for Electric Fans—25th May 1940—12 NOON."

		F.O.R.
(1) Fans Electric, Ceiling, 110 volts, 25 cycles, with three or four blades, 3-speed regulator, suspension shackle canopy, etc., complete ..	2	Maddur
	4	Oorgaum
(2) Do do 220 volts do do ..	2	Maddur
(3) Fans Electric, Desk, 110 volts, 25 cycles, 16″ fan blades, 3-speed regulators, with standard length of cord and spare adopter ..	8	Oorgaum

M. HAYATH,
For *Chief Electrical Engineer.*